•

·

.

.

.

Signal of the second of the se

.

.

Anthony M. Tung 36 Cooper Square 5R New York, NY 10003 212-533-3124 anthonym.tung@verizon.net

7 January 2015

Honorable Nicholas S. Musso, A.I.A. Chairman Vieux Carré Commission The City of New Orleans, LA

TESTIMONY IN REGARD TO 1036 ESPLANADE AND 1040 ESPLANADE

Dear Chairman Musso and Honorable Members of the Commission,

My name is Anthony Tung. I am a former member of the New York City Landmarks Preservation Commission (from 1979 to 1988) and a professor on international urban preservation at MIT (2006) and Columbia University (2012); and the author of *Preserving the World's Great Cities: The Destruction and Renewal of the Historic Metropolis*.

I offer this testimony in no one's employ and at my own expense as a friend of the Vieux Carré, one of the singular historic townscapes in the United States.

The matter before you, a proposal to renovate two properties and to adapt all, and or parts, of these existing structures for use as a restaurant has the potential to profoundly impair the unique character of the Vieux Carré by threatening its long-term viability as a place for people to live.

In making this assessment I am informed by my professional involvement in several suits brought by Smith Stagg, L.L.C., on behalf of Peter Yokum, a home owner in the Vieux Carré who is suffering from unregulated and (I believe) illegal violations of the city's noise ordinance due to excessive sound levels from nearby restaurants and bars.

Thus, having walked the Vieux Carré numerous times in the past as a visiting lecturer and having recently examined the quarter in the company of leading experts on nuisance noise, I am aware of the debilitating impact of unchecked restaurant, bar, and club noise on the residential quality of life.

The extreme sound levels on Bourbon Street are shocking and pertain directly to the matter before you. Given that the eastern portion of the French Quarter remains a generally quiet place of residential occupancy, and that the eastern boundary of the Vieux Carré (Esplanade Avenue), is remarkably idyllic: allowing an open-air restaurant at 1036 Esplanade and 1040 Esplanade courts the demise of residential habitation. As on Bourbon Street, heightened ambient noise from the proposed open-air restaurant can lead to a violent escalation of clamor, making nearby residential occupancy a nightmare.

Like in Venice, Bruges, and other historic cities in Europe and North America, a negative syndrome of decline can follow as, one by one in a domino effect, various residential occupants are driven out. This 'Venice-like' syndrome is already activated in the Vieux Carré where, in recent decades, residential population has dwindled, tourism services have mushroomed, and residential services have shrunk. (See attached note for details.)

Thereby, I believe the current proposal warrants your closest scrutiny.

In terms of it's architectural features:

- 1. The impact of excessive noise can not be controlled if the restaurant function remains unenclosed behind walls—because regardless of the intent or assurances of the new property owner, once an open-air facility is approved, it will be extremely difficult to police noise pollution should a less sensitive occupant ever gain possession. This would constitute a permanent on-going injury to the district's well-being. It is a grossly inappropriate change of use.
- 2. Preservation of the strikingly handsome historic residential character of Esplanade Avenue will be injuriously affected as the restaurant's open-air commercial presence intrudes on its quiet domestic character.
- 3. The street facades and massing of the proposed structure constitute an alien building type in the historic urban landscape. Its forms are more consistent with a Post-war suburban commercial strip than with the "quaint and distinctive" character of the "toute ensemble" of the Spanish Colonial/French Colonial/American-Creole-Antebellum entrepôt. It is grossly inappropriate in terms of architectural form.
- 4. Finally, given the Vieux Carre Commission's long history of requiring new infill architecture consistent with a French Quarter Style—with traditional-looking structures that complete existing street-walls—approval of the current proposal raises a fundamental regulatory question: Is the commission now abandoning a decades-old and highly effective policy? —a policy which has made the Vieux Carre one of the most beloved and beautiful historic districts in America.

Sincerely, Anthony M. Tung

Notes: As per Tourism Gentrification: The Case of New Orleans' Vieux Carre by Kevin Fox Gotham in *Urban Studies Magazine*, Vol. 42, No. 7, June 2005:

- Between 1940 and 1970 the population of the Vieux Carre plummeted from 11,053 to 4,176, a loss of more than 50-percent, even as the population of the city as whole increased by 30-percent.
- From 1950 to 1999, the number of souvenir and t-shirt shops increased from 26 to 110; retail apparel stores increased from 14 to 42; music clubs increased from 7 to 27; hotels increased from 21 to 40; and art galleries increased from 10 to 40.
- From 1950 to 1999, the number of groceries decreased from 44 to 4; miscellaneous food stores declined from 44 to 19; hardware stores from 31 to 1; laundry services from 24 to 2.

•

1

.



ROBERT L MILLER

A R C H I T E C T 1491 West Highway 98 Mary Esther, Florida 32569 850-581-2174 - Phone 850-581-0295 - FAX RLM@RLMarch.com

BUILDING CODES CONSULTANT
CONTINUING EDUCATION SEMINARS
PROFESSIONAL WITHESS
ARCHITECTURAL SERVICES

January 7, 2015

RE: Café Habana - Proposed Design Documents for VCC Submittal

1040 ESPLANADE AVE / 1324 NORTH RAMPART,

1036-1038 ESPLANADE AVE

NEW ORLEANS, LA 70116

By: Rozas - Ward Architects & Palmisano Contractors

This review is at the request of concerned property owners adjacent to and in the vicinity of the proposed project. Use of this review is restricted to purposes of such persons.

The documents provided to the State Fire Marshal for "PRELIMINARY REVIEW" (see Fire Marshal review P0457374 dated October 29, 2014) were not dimensioned to allow for the plan reviewer to determine accurate occupant load calculations. Those documents indicated both first and second floor were intended for assembly use. Each floor had a kitchen to serve the dining on the respective floor. Square footage was indicated for only a portion of the areas of each floor which was assumed by the Fire Marshal reviewer for occupant load calculation. Due to the insufficient information being provided, the reviewer was unable to calculate correct occupant loads.

The documents presented for review now indicate a mixed occupancy of Assembly (Group A-2), to be used as a dining facility, and Residential (Group R-1 or possibly R-2). The plans indicate the intent to provide sprinkler protection which is required for both occupancy classifications. There does not appear to be any fire resistant rated separation indicated so the assumption would be that the project is being proposed as "non-separated" occupancy classification and compliance with IBC Section 508.3 would be required. In those circumstances, the entire facility must be protected in accordance with the most restrictive requirements of the occupancies.

Though this is a renovation of an existing facility, due to the extent of renovation construction, change of use, and reconfiguration of space, it is required to comply with Codes and Standards for new construction. The primary Codes enforced for new construction are the currently adopted Life safety Code (NFPA 101 - 2012) and the International Building Code (IBC - 2012) in addition to Orleans Parish and City of New Orleans ordinances and the additional Standards referenced by those Codes.

Upon review of the current revised documents under consideration for this project, the following issues are observed and deemed appropriate for comment:

The first floor of 1036 Esplanade was originally occupied as mercantile occupancy classification.
That space has now been defined as what appears to be dining facilities and attached commercial
kitchen defined in the IBC as occupancy Group A-2. For purpose of understanding, Group A-2 is
defined as:

Assembly uses intended for food and/or drink consumption including, but not limited to:

- a. Banquet halls
- b. Casinos (gaming areas)
- c. Nightclubs
- d. Restaurants, cafeterias and similar dining facilities (including associated commercial kitchens)
- e. Taverns and bars
- The commercial kitchen exhaust at the roof appears to be within 20 feet of the open patio of the adjacent residence. While not necessarily a Code issue, the grease laden aromatic vapors produce by the volume of cooking at this facility would prove objectionable which was noted in prior VCC comments.

- 3. Occupant load calculations in the submitted plans do not appear to be as defined by the various Codes and Standards enforced by the Louisiana State Fire Marshal or the City of New Orleans. Those methods are documented as follows:
 - a. Demarcation of a "path of egress" within assembly areas intended for use as dining facilities so as to exclude those paths from areas used to calculate the occupant load is not found in either the NFPA 101 or the IBC in dining rooms. The result provides for an artificially reduced occupant load.
 - b. The occupant load (number of occupants in a space) of a dining area is calculated at 15 square feet per occupant based on the entire area to be occupied with the exception of fixed obstructions such as cabinetry or appliances used for service or structural members. Alternatively, fixed seating can be used and counted as such. No fixed seating was indicated, only an area designated for such.
 - c. Calculation of occupant load based on 15 square feet per occupant at the first floor interior dining areas indicated on the plans appears to be at least 60 as the area in question appears to enclose approximately 907 square feet excluding corridors and the bar. The plans indicate an occupant load of 57 without specifically showing the individual "fixed seating.
 - d. In addition, the exterior Dining under the canopy and the courtyard area having the same occupancy use must have the occupant load calculated at 15 square feet per occupant in accordance with the adopted codes.
- 4. This interior dining is proposed to egress through the area labeled "EXTERIOR PATIO". Again, the "egress path" demarcation falsely reduces the actual occupiable area to project an occupant load less than the appropriate calculations would provide. The Codes do not provide for reduction of occupant load due to egress paths which are properly included in the area used in the calculations.
- 5. A means of egress is proposed through an alleyway between this project and the adjacent residence. That alleyway has been measured at 32 inches maximum with reduction at the gate point by utility meters and electrical panel. That route is just to the left of a door indicated as an ADA Accessible door. The indicated route of egress to the public way from that door is through this alleyway thus designating the alley as an accessible route. Investigation of the 2010 ADA/ABA adopted for review by the State Fire Marshal does not indicate that the width is sufficient for accessible egress. The minimum egress width would require not less than 44" in accordance with the NFPA 101 and IBC and additionally would require fire resistance rated corridor protection which is not indicated. Attached photographs indicate the existing electrical panel and other meters protrude into the egress width up to 10" into the clear width in an accessible route. In accordance with the 2010 ADA Standard Section 307.2, protrusion is limited between 27 and 80 inches above the floor of an accessible route to 4" into an accessible route which further precludes this alley from use as an egress route.
- 6. Additional route protection includes the following issues observed:
 - a. Rated corridor protection (minimum one hour is required but neither property appears to have those exterior bearing walls rated in accordance with IBC Table 601).
 - b. Level route (that alleyway is not paved as required by accessibility codes and standards)
 - c. Clear width (the gate at the Esplanade Avenue sidewalk exit from the alleyway is of the required 32 inches minimum measured with the gate opened 90 degrees)
- 7. The proposed dining at the second level on top of the existing filling station canopy has similar Code misinterpretations. The area there, though shown as reduced by low partitions to provide for a smaller occupant load, has the same "path of egress" demarcated so as to eliminate that path from the calculable area. The drawings indicate a calculated occupant load based on concentrated occupant load at 7 square feet per occupant and indicates a load of 77 occupants. Additional

notations indicate that somehow, the State Fire Marshal will condescend to reduce that area to an allowable 49 occupants thus permitting a single means of egress from that canopy.

The Codes in fact require the "calculated" occupant load be the minimum and do permit that load to be exceeded only if egress facilities and life safety protection are provided for the increased occupant load.

- 8. Further, regarding the seating on top of filling station canopy, the apparent area involved is 782 square feet which at 7 square feet per occupant is 112 occupants. The apparent intention with the proposed seating indicated at 7 square feet per occupant is that the space on top of the filling station canopy is to be used for concentrated load use such as found on a dance floor or other party type use similar to what is observed during Mardi Gras and other festivals in New Orleans. Due to the occupant load on the canopy exceeding 49, two means of egress are required by both the NFPA 101 and IBC from the filling station canopy but only a single means of egress is provided in these drawings.
- 9. Additional occupancy calculations are questionable at the ground floor where the only "occupied" dining area is indicated as partially under the filling station canopy. The Codes require all occupiable space in assembly occupancies to be accounted for. The entire space designated as "CATERING COURTYARD" and "EXTERIOR PATIO" is occupiable and while planters and other devices are indicated on the drawings, precise delineation of the occupiable space is not indicated. The NFPA 101 in Table 7.3.1.2 for Occupant Load Factors requires assembly use areas of "Less concentrated use, without fixed seating" to use 15 square feet for the net square footage of the area. Additional information is required to determine the precise occupant load allowed. The area in question appears to have a scaled square footage of 3,085 which when divided by 15 produces a calculate occupant load at the outdoor dining and patio of 206 occupants.
- 10. The total calculated occupant load of the ground floor dining and courtyard areas appear to be 272 in addition to the facility's upper floor of 112 for assembly in addition to the load of the residential occupancy. The apparent total occupant load then would be 384 subject to accurate dimensions and specific use being provided in future final construction drawings required for review.
- 11. Structurally, the existing filling station canopy, being a roof provided for weather protection, was not intended for human occupancy. If built under current Codes that canopy would have in addition to the loads imposed by the structure itself a required live load of 20 pounds per square foot which is sufficient for typical loads imposed by weather. However, the required design live load for assembly occupancy as proposed is 100 pounds per square foot [see IBC Table 1607.1]. This required load is 500 percent greater than the design capacity requirements of a filling station canopy. There is no evidence of increased structural support for that required load. If preservation of this existing facility is of concern, then any structural modifications should meet the local ordinances for preservation.

Though the drawings available for review are incomplete without any precise dimensions, I was able to transform them into drawings from which all dimensions and areas noted above were garnered. In my opinion, no further permissions should be granted without full submittal to the State and Local authorities and receipt of documents indicating compliance with the Codes and Standards and accessibility requirements for mobility impaired persons.


Should any questions arise regarding any of the comments above, please feel free to contact me.

Sincerely:


Robert Miller Architect



Photo showing building electrical panels and utility meters protruding into alley



Alley from public sidewalk showing the gate and unleveled ground surface Also shows plumbing drain cleanout and hose-bibb protrusion into alley



Utility panel box protruding into ally between gate and public sidewalk Note the non-level walking surface between the gate and public sidewalk

English of the second control of the second

.

AFFIDAVIT

STATE OF LOUISIANA PARISH OF ORLEANS

£. + 27

BEFORE ME, the undersigned Notary, came and appeared: ARNO S. BOMMER

A person of the full age of majority, domiciled in Harris County, Texas, who, after being duly sworn, did depose and say:

That he is employed as a consultant certified by the Institute of Noise Control Engineering, specializing in the science of acoustics, noise and vibration at Collaboration in Science and Technology Inc., in Houston, Texas;

1. Board Certification

I am board certified by the Institute of Noise Control Engineering, a process that involves qualifications and rigorous testing.

2. Previously certified by the Civil District Court as an expert in noise measurement and interpretation of the City of New Orleans Noise Ordinance and methodology previously relied-upon by Judge Ethel Simms Julien, in finding a nuisance bar in violation of injunction.

In previous cases, Hon. Ethel Simms Julien and the Hon. Christopher Bruno accepted me as an expert in noise and relied upon my findings.

I offer the following opinions with respect to the Café Habana based on the plans dated November 18, 2014:

- 1. A typical "busy" restaurant sound level is about 65 dBA. A very noisy restaurant can be 80 to 85 dBA.
- 2. The outdoor portions of Café Habana may occasionally exceed 80 dBA.
- 3. People tend to talk louder when there are other nearby sources of noise. The traffic on N. Rampart and Esplanade as well as the HVAC equipment and proposed fountains will provide background noise that patrons will have to speak over, causing them to speak with raised voices.
- 4. When the curtainwall doors are open, there will be two effects. By itself, the added noise from under the canopy might raise sound levels in the patio by 1 to

- 5 dBA. In addition, this increase may also cause the people in the patio area to speak louder, further increasing levels.
- 5. Other potential source of excessive community noise include HVAC condensing equipment at grade by the stairwell, a condenser unit on the roof, kitchen hood exhaust vents, doors slamming, and wait staff handling plates, trays, and silverware.
- 6. Although the existing two buildings along the residential property line provide a partial noise barrier, there is a large gap between these buildings adjacent to the stairs with only a low wall (about 6-ft tall). Sound from the courtyard and patio can travel directly through this gap to the adjacent residences.
- 7. The top of the stairs and 2nd-floor walkway are located right at the gap between the buildings. It appears from the plans that people on these stairs and walkway can look right down onto the adjacent residential property, and any sounds they make will travel directly onto the residential property.
- 8. The existing neighboring building on Rampart can reflect sounds from much of Café Habana through the gap between the buildings towards the adjacent residences.
- The roof of the existing 2-story building also has a large overhang that can reflect sound from the courtyard and patio back down to the ground at the residences.
- 10. Taking into account distance effects, sound from a 65 dBA "busy" restaurant would be reduced to about 59 dBA at 50 ft (the approximate distance from the center of the restaurant to the nearest residences). This would be steady restaurant noise. If the restaurant sounds were between a "busy restaurant" and a "noisy restaurant", then sound levels at the neighboring residences would exceed 60 dBA with an L₁₀ measurement (the sound level exceeded 10% of the time).
- 11. In addition to the steady noise from the restaurant, there are often periodic louder sounds from loud conversations (laughing, very loud talking, etc.) or from events such as things being dropped. Brief sounds from people talking on the stairs can also be very loud. These types of sounds are likely to increase maximum sound levels from the restaurant at the neighboring residences to 65 dBA or higher.
- 12. The restaurant is in the VCC zone where the nighttime ordinance is an L₁₀ of 60 dBA and an Lmax of 65 dBA.
- 13. The adjacent residences are in the VCR zone where the nighttime ordinance (after 10 pm) is an L_{10} of 55 dBA and an Lmax of 60 dBA. The applicable limits of

- the New Orleans noise ordinance are from the receiving land use, not the use of the sound source.
- 14. The HVAC equipment is rated at 66 to 69 dBA at 10 ft. The three closest units at grade range from 3 ft to 10 ft from the property line. Although there is a 6-ft wall at the property line, there are also adjacent walls and the underside of the stairs and balcony that will reflect sound over the wall. As a result, the HVAC noise is expected to produce sound levels over 70 dBA at the property line, greatly exceeding the nighttime noise ordnance and possibly exceeding the daytime ordinance.
- 15. There is line-of-sight from adjacent residences to the rooftop kitchen vent fan and walk-in-cooler condenser. I do not have any specific noise data for these, but it is likely that they will also produce excessive noise at the property line.
- 16. The restaurant sound levels from the HVAC equipment and from patrons are expected to regularly exceed the residential noise limit of the New Orleans noise ordinance after 10 pm.
- 17. With a possible standing-room capacity of over 400 people that was testified to at a committee meeting, expected sound levels could be 10 dBA louder due to the number of added patrons plus the expected effect of patrons having to further raise their voices.
- 18. The adjacent residences at 1026 Esplanade and 1028 Esplanade have backyards that are currently shielded from traffic noise by the buildings between the backyards and the roads, and these quiet backyards and their overlooking windows will be most affected by noise from Café Habana.
- 19. The proposed establishment would significantly alter the soundscape in the adjacent residential areas, adversely affecting the neighborhood's quaintness and the *toute ensemble* of the Vieux Carre. It would increase foot traffic along N. Rampart and Esplanade. Not only would patrons make sound within the site, they would also make sound from sidewalks while they are on a waiting list for a table. Because of this, the increased noise effect would spill out from the restaurant into the surrounding area.

The foregoing facts are known personally to Affiant, Arno S. Bommer.

AŔNO S. BOMMER

Sworn to and subscribed before me, This 7th day of January, 2015.

(Notary Signature)

(Print Notary name and #)
Notary Public
State of Louisiana

Stephen H. Wussow, Notary Public and Attorney at Law (LSBA No.35391) 365 Canal Street, Suite 2850 New Orleans, Louisiana 70130 Parish of Orleans, State of Louisiana My Commission is for Life. $\mathbb{E}_{\mathcal{L}} = \mathbb{E}_{\mathbb{R}^{n}} \mathbb{E}_{\mathbb{R}^{n}} = \mathbb{E}_{\mathbb{R}^{n}}$

4



Comprehensive Compliance Solutions

9744 Cal Road Baton Rouge, LA 70809

January 7, 2015

Mr. Stuart Smith One Canal Place 365 Canal Street, Suite 2850 New Orleans, Louisiana 70130

Dear Mr. Smith,

I retired from the Department of Environmental Quality (LDEQ) on January 1, 2010 after 25 years of service. My resume is attached. I have reviewed LDEQ documents related to the remediation of property located at 1036-1038 and 1040 Esplanade Avenue in New Orleans, LA. A developer wants to build a restaurant called Café Habana at that location. I have some concerns in that respect. My concerns are as follows:

- 1) the removal of some of the contaminated soil and six steel underground storage tanks that had been buried for more than sixty years is not adequate because a significant amount of hazardous substances remains on the property.
- 2) If the ultimate purpose of air testing is to determine the potential health impact to the public and reduce uncertainty in the assessment, insufficient air testing was done during the closure. Additional testing has to be conducted prior to construction of this restaurant in my opinion.

 3) The developer is required to notify LDEQ that the intended land use has changed so that LDEQ can re-evaluate the contaminated areas that was of interest in the remediation. (See aftached conveyance notice, indicating the property has not been released for non-industrial use.) I have not found any such land use change notification in the public records at LDEQ.

- 4) A groundwater sample should have been taken since RECAP standards were exceeded at a depth of 8 feet, a depth near or below the water table.
- 5) Soil samples should have been taken at the property line since the samples taken on the southern end of Tank 2 and Tank 3 exceeded RECAP standards and were in close proximity to neighboring property.
- 6) Insufficient testing was performed and therefore the possibility that contamination has spread to neighboring properties cannot be eliminated.

Sincerely,

Richard Brackin

Leaaf

June 18, 2013 Leaaf# WIL-007

Mr. Tom Harris Admin.
UST and Remediation Division
LA DEQ
P.O. Box 4312
Baton Rouge, LA 70821-4312

RE: Conveyance Notice 1040 Esplanade Ave New Orleans, LA 70116 (Orleans Parish) Facility ID No. 36-019386

Al No. 184805

DECETAED

TOUR ST 5013

TOUR S

Kenyowia	n Sauce & Ovision
Mobraet	
Mapager	
Team Loades _	
Al#:	
TEMPO RISH	;:
il linear City	; F#E.8420" (,

Mr. Harris:

Leaaf Environmental, LLC (Leaaf) is submitting this letter documenting the filing of the Conveyance Notice for the above referenced site.

The Conveyance Notice was filed with Orleans Parish conveyance records on June 12, 2013. The original and one (1) photocopy of the notice are attached for LDEQ records:

If you have any additional questions regarding this matter, please contact Jesse Hoppes or Jim Blazek at (504) 342-2687.

Sincerely,

Holly (0) Johnston Bookkeeper

RECEIVED

JUE. Tu

SOUTHEAST REGISTIAL

Le	aaf	env	rironn	nental,	llc
----	-----	-----	--------	---------	-----

www.leaaf.com

812 Rupp Street, Gretna, LA 70053 New Orleans office: 2828 Burgundy, New Orleans, LA 70117 Lafayette office: 161 Glynwood Avenue, Lafayette, LA 70506 (504):342-2687 Fax (504):342-2715

Adjudication (La. R.S. 49:955 APA Hearing Requirements

"§955. Adjudication; notice; hearing; records

A. In an adjudication, all parties who do not waive their rights shall be AFFORDED AN OPPORTUNITY FOR HEARING after reasonable notice.

B. The notice shall include:

1) A statement of the time, place, and nature of the hearing;

2) A STATEMENT OF THE LEGAL AUTHORITY AND JURISDICTION UNDER WHICH THE HEARING IS TO BE HELD;

3) A REFERENCE TO THE PARTICULAR SECTIONS OF THE STATUTES AND RULES INVOLVED

(4) A short and plain statement of the matters asserted.

EVIDENCE ON ALL ISSUES OF FACT INVOLVED AND ARGUMENT ON ALL ISSUES OF OPPORTUNITY SHALL BE AFFORDED ALL PARTIES TO RESPOND AND PRESENT LAW AND POLICY INVOLVED and to conduct such cross-examination as may be required for a full and true disclosure of the facts.

distinctive character of the Vieux Carre section of the City of New Orleans may not be injuriously in order that the quaint and affected...

New Orleans v. Pergament, 198 La. 852, 856 (La. 1941) and City of New Orleans w Act 139 of 1936, Section 22A of Article XIV of the Constitution, as cited in City of mpastato, 198 La. 206, 208 (La. 1941)

Page 1, Historic Continuty

19th and 20th centuries. The three centuries in the 18th Century and followed in the of living and building are what have created the "distinctive character" of the Vieux Carre." buildings, and landmarks was established "The overall pattern of streets, lots, Created the Vieux Carre.

Pages 2-3, VII oute Ensemble,

Commission, are to be taken as valid and principles and regulatory details of these ensemble, "The carefully compiled As to the preservation of the 'toute guidelines, based on fifty years of experience by the Vieux Carre

VCC Design Guidelines: Major Components of Vieux Carre Distinctiveness


- Scale of the District
- Texture of Typical Street Scene (Pattern created by wall openings, shutters, balconies, galleries, ironwork, cornices,
- Typical Building Site Plan

VIII WECHANICAL, PLUMBING AND ELECTRICAL EQUIPMENT

design available and shall be located so as to not detrimentally affect the buildings or its B. Air conditioning and other mechanical equipment should be of the most compact neighbor's visual or sonic environment.

* * *

* * * -VCC Design Guidelines, 1986, pg. 49



医表情性 人名英格兰人姓氏克里特 医克里特氏试验 医电影 血血管 机电压管

Sec. 10236. - Restrictions as to broberty near schools, churches, etc.

consumed on the premises WITHIN 300 cabaret or other place WHEREALCOHOLIC BEVERAGES ARE SOLD AT RETAIL, to be FET OF ANY playground, CHURCH, public that NO PERMITSTALL BEGRANTED for policy of this section and section 10-238 (a) It is hereby declared the sense and the opening of any barroom, saloon, library, or school


A. A. J. C. C. Miller, P. S. Charles


7 - 3 --- - --- - - --- v..... .




Maria Company of the second second second











...



:

: ::

The state of the s

Organizations Opposec

- Faubourg Marigny Improvement Association
- VCPORA
- French Quarter Citizens
- Louisiana Landmarks Society
- Foundation for Historical Louisiana
- Citizens Action Committee

Article 8, Section 8.1 and the Design Guidelines require the Commission to review proposed changes in use.

The Commission and staff ignore the authority requiring review of changes of use:

that approves and permits proposed changes in use; as Article 8, section 8.1 of the Comprehensive Zoning Ordinance explains, "Staff would like to affirm that the VCC is not the review entity he VCC is responsible for reviewing the proposed, physical changes to the building that are necessary in order for the building to function as the proposed, new use."

-8/26/14 Staff Analysis and Recommendation

CONPERENTALVE ZOUING OHDINAL

Ordinithing 18,565 G. C. S. Inly 9, 1983, ps amended.

ÁRTIÉLE.KVI az RT Vieuk Carre Rogificitiel District Bogululows

pierson I. The regulations we free if the Attain we threinkise regulation in the confidence of the con

BEOTION B. Ule Heardwines.

- Ma, redipacty remain that I in termed by the Ulterion, Batety and Parmite Lee arty ubulge.

 (1) In the two the attent and the little and the result of the shall liver head.

 I have the attent current Contribution, they wise no cleades of excitor the regimes because the current course the two cleans and the result by the Vene Care Contribution that the requirements because the contribution with the strates are cleaned by the contribution that the contribution of the course the contribution, and it and a boarday spirit, the approver upon characteristic the contribution the remains the contribution the remains the contribution that the contribution and the contribution that the contribution contribution the remains the contribution that the
 - s. The Mashriti pharacer of the Wens Cours at all not be befundately withouted
- b. Bignd widels, lave ganded, at divisioning put of Legying 1817,'s tha character of Our Visua Garra sheet, not in principles.
- o, Belleding designo desil de in susception which the Cearliscope all discounts care as the Vienes Court.
- A. The rices of the Plator Carre in it place of unique offerest and charterey shall ..
- Gullica' to n-quash perpit issued by the Viara Care Currethion for not element is to istendable your the full of a same shall be used only for the full with
- ... Any use perceived in the C-byte Femily. Intiffe.

- b. Mithyla-family awallings
- 1-1. Inclosed chirely gumper.
- . e. 'Eurpeony buildings and 1986, curtionerally incleaned to uny...(fire above usps.

same use, or for any other use not otherwise prohibited in this district, subject to the following conditions and safeguards:

1. The historic character of the Vieux Carre shall not be injuriously affected.

2. Signs which are garish or otherwise out of keeping with the character of the Vieux Carre shall not be permitted.

3. Building designs shall be in harmony with the traditional architectural character of the Vieux Carre as a place of unique interest and character shall not be impaired: building until and unless a special permit shall have been issued by the Vieux Carré Commission; except that where no by the Vieux Carré Commission shall not be required. Where Safety and Permits, for any change in the use of any existing any change in exterior appearance is contemplated, the Vieux change of exterior appearance is contemplated such permit Carré Commission shalf-fiold a hearing, and if it approves such change, it shall issue a special permit to confinue the Article 8, Section 8.1 provides:

/IEUX CARRE COMMISSION



DESIGN CUIDELINES

4ARCH 18, 19B

AYENDED SBYTEMBER 14, 199

Reprints May, 1987

The Design Guidelines provide:

"The Commission has already acknowledged its authority to disallow uses of property that are detrimental to the Vieux Carre."

"The Vieux Carre Commission is not bound to allow every permitted use to be accommodated in every building."

-VCC Design Guidelines, 1986, pg. 57

The Vieux Carre Commission finds the Cuidelines exercise of its authority. are necessary, controlling, and a permissible

"As new growth alerted the world to the charms of the Vieux Carre," controls became necessary so that large scale projects and grand schemes would not erode the very charms that underlay the Quarter's popular success."

-VCC Design Guidelines, 1986, pg. 2

guidelines, based on fifty years of experience by the Vieux "The carefully compiled principles and regulatory details of these Carre Commission, are to be taken as valid and tested." VCC Design Guidelines, 1986, pg. 57

the Vieux Carre as a whole ... by following these guidelines, the property owner is doing his part to help the Commission protect the fragile, irreplaceable environment of this historic district." "The Commission has to consider each design on its
own merit as well as its effect on its neighbors and

Each proposal's "effect on its neighbors." and effect to the "tout ensemble" is to be considered by the Commission

- Affidaxit and Testimony of Arno Bommer.
 Statements of neighborhood residents.
 Statement of Anthony Tung.
 The Staff and the Commission itself has noted the detrimental effects of this proposal.

Detrimental Effects noted by Staff and Commission

The Staff of the View Caure Commission has already noted that this design erodes the historic character of the area, by noting that it. is curious to know why the residential unit list being maintained in an environment that would not be conductive to peaceful living."

-3/12/13 Staff Analysis:

-3/12/13 Staff Analysis:

"installation of the vents on the river-side slope is unsuitable due to the effects on neighboring properties."

- 10/1/14 Staff Analysis:

"The proposal presents questions negariding the addition of noise and traffic to the corner."


"The proposal presents questions negariding the addition of noise and traffic to the corner."

"The proposal presents questions negariding the addition of noise and traffic to the corner."

"staff already has concern that the use of the canopy top as an occupy-able space "change(s) the defining characteristic of the building and its site and environment." The Committee should be very thoughtful when considering the proposed use for the canopy, considering it is the defining feature of that structure.

"staff contends that exhaust stacks are better placed on the river-side roof slope ,, but is concerned about the effect on neighboring properties."

Comprehensive Zoning Ordinance Open Space Requiremen The application, as proposed, will violate the



"A minimum of 30% open space for interior sites and 20% for corner sites shall be maintained"


SUMMARY

- The Design Guidelines have been completely ignored in evaluating this proposal;
- Open Space requirements will not be met;
- The Commission and its Staff have acknowledged that the proposal will have detrimental effects to the historic character of the neighborhood and the "tout ensemble".

Vieux Carre Commission Design Guidelines

•No citation to nor mention of the design guidelines throughout the entirety of this application.

and Commission's choice to ignore its own Design Guidelines suggest that the decision will be found to be arbitrary and capricious. Any approval given to the application, given the Staff arbitrary and capricious.



NO HABANA!

		Indexito NO HABANA!
Tab	Date	Description
1	01/07/2015	Anthony M. Tung Expert Report
A		Anthony M. Tung Curriculum Vitae
2	01/07/2015	Robert L. Miller Expert Report
A		Robert L. Miller Curriculum Vitae
В		Habana with 200 People
С		Habana with 400 People
3	01/07/2015	Arno S. Boomer Affidavit
Α		Arno S. Boomer Curriculum Vitae
В		Noise Impact Aerial
4	01/07/2015	Richard Brackin Expert Report
Α		Richard Brackin Curriculum Vitae
5	01/07/2015	Original PowerPoint Presented at VCC Meeting
6	12/19/2014	Café Habana Plans
7		Map Showing Application Illegality

	•	

Anthony Tung

PRESERVATION EXPERT

Anthony M. Tung 36 Cooper Square 5R New York, NY 10003 212-533-3124 anthonym.tung@verizon.net

7 January 2015

Honorable Nicholas S. Musso, A.I.A. Chairman Vieux Carré Commission The City of New Orleans, LA

TESTIMONY IN REGARD TO 1036 ESPLANADE AND 1040 ESPLANADE

Dear Chairman Musso and Honorable Members of the Commission,

My name is Anthony Tung. I am a former member of the New York City Landmarks Preservation Commission (from 1979 to 1988) and a professor on international urban preservation at MIT (2006) and Columbia University (2012); and the author of *Preserving the World's Great Cities: The Destruction and Renewal of the Historic Metropolis*.

I offer this testimony in no one's employ and at my own expense as a friend of the Vieux Carré, one of the singular historic townscapes in the United States.

The matter before you, a proposal to renovate two properties and to adapt all, and or parts, of these existing structures for use as a restaurant has the potential to profoundly impair the unique character of the Vieux Carré by threatening its long-term viability as a place for people to live.

In making this assessment I am informed by my professional involvement in several suits brought by Smith Stagg, L.L.C., on behalf of Peter Yokum, a home owner in the Vieux Carré who is suffering from unregulated and (I believe) illegal violations of the city's noise ordinance due to excessive sound levels from nearby restaurants and bars.

Thus, having walked the Vieux Carré numerous times in the past as a visiting lecturer and having recently examined the quarter in the company of leading experts on nuisance noise, I am aware of the debilitating impact of unchecked restaurant, bar, and club noise on the residential quality of life.

The extreme sound levels on Bourbon Street are shocking and pertain directly to the matter before you. Given that the eastern portion of the French Quarter remains a generally quiet place of residential occupancy, and that the eastern boundary of the Vieux Carré (Esplanade Avenue), is remarkably idyllic: allowing an open-air restaurant at 1036 Esplanade and 1040 Esplanade courts the demise of residential habitation. As on Bourbon Street, heightened ambient noise from the proposed open-air restaurant can lead to a violent escalation of clamor, making nearby residential occupancy a nightmare.

Like in Venice, Bruges, and other historic cities in Europe and North America, a negative syndrome of decline can follow as, one by one in a domino effect, various residential occupants are driven out. This 'Venice-like' syndrome is already activated in the Vieux Carré where, in recent decades, residential population has dwindled, tourism services have mushroomed, and residential services have shrunk. (See attached note for details.)

Thereby, I believe the current proposal warrants your closest scrutiny.

In terms of it's architectural features:

- 1. The impact of excessive noise can not be controlled if the restaurant function remains unenclosed behind walls—because regardless of the intent or assurances of the new property owner, once an open-air facility is approved, it will be extremely difficult to police noise pollution should a less sensitive occupant ever gain possession. This would constitute a permanent on-going injury to the district's wellbeing. It is a grossly inappropriate change of use.
- 2. Preservation of the strikingly handsome historic residential character of Esplanade Avenue will be injuriously affected as the restaurant's open-air commercial presence intrudes on its quiet domestic character.
- 3. The street facades and massing of the proposed structure constitute an alien building type in the historic urban landscape. Its forms are more consistent with a Post-war suburban commercial strip than with the "quaint and distinctive" character of the "toute ensemble" of the Spanish Colonial/French Colonial/American-Creole-Antebellum entrepôt. It is grossly inappropriate in terms of architectural form.
- 4. Finally, given the Vieux Carre Commission's long history of requiring new infill architecture consistent with a French Quarter Style-with traditional-looking structures that complete existing street-walls-approval of the current proposal raises a fundamental regulatory question: Is the commission now abandoning a decades-old and highly effective policy? —a policy which has made the Vieux Carre one of the most beloved and beautiful historic districts in America.

Sincerely, Anthony M. Tung

Notes: As per Tourism Gentrification: The Case of New Orleans' Vieux Carre by Kevin Fox Gotham in Urban Studies Magazine, Vol. 42, No. 7, June 2005:

- Between 1940 and 1970 the population of the Vieux Carre plummeted from 11,053 to 4,176, a loss of more than 50-percent, even as the population of the city as whole increased by 30-percent.
- From 1950 to 1999, the number of souvenir and t-shirt shops increased from 26 to 110; retail apparel stores increased from 14 to 42; music clubs increased from 7 to 27; hotels increased from 21 to 40; and art galleries increased from 10 to 40.
- From 1950 to 1999, the number of groceries decreased from 44 to 4; miscellaneous food stores declined from 44 to 19; hardware stores from 31 to 1; laundry services from 24 to 2.

Anthony M. Tung 36 Cooper Square, 5R New York, New York 10003 tel and fax: 212 533-3124

email: anthonym.tung@verizon.net

RESUME

author: Preserving the World's Great Cities:

The Destruction and Renewal of the Historic Metropolis

Hardcover: Clarkson Potter/Random House, New York, 2001 Paperback: Three Rivers Press/Random House, New York, 2002 Japanese language edition: Kaiji Shobol Publishers, Kyoto, 2006

nominations:

National Book Awards/Non-Fiction, nominated by Random House USA, 2002 PEN/Architectural Digest Award, nominated by Random House USA, 2002

· Publishers Weekly, July16, 2001:

"This is an important contribution not only to the literature of urban studies and city planning, but to architectural history and sociology."

- The San Francisco Chronicle, October 14, 2001
- · Business Week, October 22, 2001:

"Masterly . . . This far-reaching book weaves well-told tales of urban destruction and renewal, using preservation and planning as the prism through which history is viewed."

- The Atlanta Journal Constitution, November 4, 2001:
 - "A remarkable chronicle of human spirit and architectural heritage."
- · The Charleston Post and Courier, November 11, 2001
- The Washington Post, November 25, 2001:

"A landmark of creative urbanism . . . Tung's breadth of vision and rapid-fire insights recall Lewis Mumford at his best."

· The Minneapolis Star Tribune, December 23, 2001:

"Beautiful and compelling . . .Tung has an acute appreciation of the value and fragility of cities."

- · The Toronto Globe and Mail, January 9, 2002
- The Charlotte Observer, February 18, 2002:

"This book fits in seamlessly with published works by other scholars of urban culture and history, most notably historian Lewis Mumford."

- · Architectural Record Online, April 2, 2002:
 - " It is an epic, or rather, 18 little epics packed into one important book."
- · Rocznick Warszawski, quarterly architectural journal, Warsaw, Poland, 2004

education: The Cooper Union, NYC, Professional Degree in Architecture, 1972

five-year course of study

awards and honors:

Prize: Fourth-Year Architectural Design, 1971

President's Award, Distinguished Alumni Citation, 1987 Alumni Representative, Board of Trustees, 1996 to 2000

historic preservation appointments:

and civic affairs: • Commissioner

New York City Landmarks Preservation Commission, 1979 to 1988

Mayor Edward I. Koch

- -evaluated for designation 200 landmarks and 12 historic districts composed of 3,500 properties
- -reviewed 2,600 proposals constituting more than \$ 3 billion of new construction associated with protected historic buildings and districts
- Member

Transition Team for Mayor David N. Dinkins, 1990

—interviewed and recommended nominees for the heads of 9 municipal agencies awards and honors:

The Village Voice, "New York's Finest," 1988

Asian American Legal Defense and Education Fund, "Justice in Action Award," 1988

lectures on the preservation of New York City:

- Comell University, Doctoral Program in Historic Preservation, Ithaca, NY, 1989
- Yildiz Tecknic Universitesi, Department of Architecture, Istanbul, Turkey, 1995
- · Municipal Department 19, Division for Planning, Vienna, Austria, 1995
- Technical University of Athens, School of Architecture, Greece, 1995
- Kyoto University, Graduate School of Historic Preservation, Japan, 1995
- Singapore Urban Development Authority, Singapore, 1995

lectures on international urban preservation:

- · The Committee to Save the City, Charleston, S.C., 1997
- · Goethe Institute of Mexico, international colloquium, Mexico City, 1998
- The Municipal Art Society, New York, 2001
- · The National Building Museum, Washington, D.C., 2002
- The New School for Social Research, New York, 2002
- The School of Architecture, University of Toronto, Ontario, Canada, 2002
- The Ontario New Democratic Party, policy conference, London, Canada, 2002
- · United States-Spain joint forum on urban development, Madrid, Spain, 2003
- · Annual Preservation Forum, key-note, Saratoga Springs, N.Y., 2003
- Columbia University Historic Preservation Program, New York, 2003
- State of New Jersey Conference on Urban Preservation, key-note, Trenton, N.J., 2003
- Los Angeles Conservancy, colloquium keynote, Los Angeles, 2003
- The Getty Conservation Institute, Los Angeles, 2003
- Williams College, Williams, Massachusetts, 2004
- Harvard University, MIT-Harvard Symposium on Urbanization in China, Cambridge, 2004
- · Ontario Provincial Conference on Urban Conservation, keynote, Hamilton, 2004
- Institute of Classical Architecture & Classical America, conference keynote, New York, 2004
- Heritage Canada Foundation Annual Conference, keynote, Saint John, NB, 2004
- · Carmichael Lecture on Urbanism, Halifax, Nova Scotia, 2005
- Florida Trust Annual Statewide Conference, keynote, Coral Gables, 2005
- · University of Miami School of Architecture, Coral Gables, 2005
- National Association of Housing, Enclave on Urban Envisioning, keynote, Charleston, SC, 2006
- · Morrison Lecture on Urbanism, New Orleans, LA, 2006
- Stadsherstel Amsterdam, Colloquium on Preservation and Housing, keynote, Netherlands, 2006
- State Historic Preservation Office, San Juan, Puerto Rico, 2006
- · City of Toronto, heritage planning workshop, Ontario, 2006
- Stadsherstel Amsterdam, Colloquium on Preservation, keynote, Netherlands, 2006
- · Colorado Preservation Inc. State Conference, keynote and workshop, Denver 2007
- City of Halifax Department of Planning, heritage planning workshop, Nova Scotia, 2007
- University of Michigan, School of Architecture and Planning, Ann Arbor, 2007
- · Preservation Foundation of Palm Beach, Florida, 2007
- Louisiana Landmarks Society, Martha Robinson Lecture, New Orleans, 2007
- · University of Cambridge, City Seminar Lecture, Great Britain, 2007
- University of Cambridge, Master Class, Great Britain 2007
- · National Trust for Historic Preservation Annual Conference, Closing Plenary, Tulsa, 2008

WNYC, AM New York: "New York and Company with Leonard Lope," 2001 radlo: WBAI, FM New York: "Behind the News with Matthew Finch," 2001 National Public Radio, "Public Interest with Kojo Nnamdi," 2002 WNYC, AM New York: "New York and Company with Leonard Lope," 2004 Canadian Broadcast Company, "Maritime Noon with Costas Halavrezos," 2004 Canadian Broadcast Company, "Maritime Noon with Costas Halavrezos," 2005

The Metropolitan Museum of Art, NYC, lectures on world architectural history, 1987-93 The New School, Graduate School of Urban Professions, NYC, course on preservation in New York, 1989 Columbia University, Historic Preservation Masters Program, thesis advisor, 2004 MIT School of Architecture and Planning, graduate course: Preserving the World's Great Cities, 2006

writing on urban affairs in periodicals:

Tung's writing on urban conservation issues has appeared in the New York Times, New York Newsday, The Toronto Globe and Mail, The Charleston Post and Courier, and Architectural Record On-Line. Currently, he is a contributing editor to ICON Magazine: a quarterly publication of the World Monuments Fund.

children's art education

and non-profit

Director and Founder

institutional administration Young People's Art, NYC, 1973 to 1980

-alternative arts education programming for New York City public schools

client institutions:

Metropolitan Museum of Art

Jewish Museum

Staten Island Museum

Staten Island Children's Museum New York State Council on the Arts

New York University Graduate School for Cultural Institution Management

Children's Television Workshop, "The Electric Company" Children's Television Workshop, "Sesame Street"

consulting and design:

Since 1973, Mr. Tung has maintained a private professional practice as a designer in such varied disciplines as architectural master planning, museum exhibition design, industrial exhibition design, industrial product design, graphic design, book design . . . completing over 200 contracts over 30 years.

Tony Tung was born on June 27, 1947 in Lansing, Michigan, and lives in downtown Manhattan with his wife, Janet Vicario, a painter and book designer. His father, George K.L. Tung, a former research chemist, was born in Shanghai, China. His mother, Rosemary Jones Tung, is the author of A Portrait of Lost Tibet (Thames and Hudson Ltd., London, 1980).

	·			
	·			

Robert L. Miller

FIRE CODE EXPERT



A R C H | T E C T 1491 West Highway 98 Mary Esther, Florida 32569 850-581-2174 - Phone 850-581-0295 - FAX RLM@RLMarch.com BUILDING CODES CONSULTANT
CONTINUING ÉDUCATION SEMINARS
PROFESSIONAL WITNESS
ARCHITECTURAL SERVICES

January 7, 2015

RE: Café Habana - Proposed Design Documents for VCC Submittal

1040 ESPLANADE AVE / 1324 NORTH RAMPART,

1036-1038 ESPLANADE AVE

NEW ORLEANS, LA 70116

By: Rozas - Ward Architects & Palmisano Contractors

This review is at the request of concerned property owners adjacent to and in the vicinity of the proposed project. Use of this review is restricted to purposes of such persons.

The documents provided to the State Fire Marshal for "PRELIMINARY REVIEW" (see Fire Marshal review P0457374 dated October 29, 2014) were not dimensioned to allow for the plan reviewer to determine accurate occupant load calculations. Those documents indicated both first and second floor were intended for assembly use. Each floor had a kitchen to serve the dining on the respective floor. Square footage was indicated for only a portion of the areas of each floor which was assumed by the Fire Marshal reviewer for occupant load calculation. Due to the insufficient information being provided, the reviewer was unable to calculate correct occupant loads.

The documents presented for review now indicate a mixed occupancy of Assembly (Group A-2), to be used as a dining facility, and Residential (Group R-1 or possibly R-2). The plans indicate the intent to provide sprinkler protection which is required for both occupancy classifications. There does not appear to be any fire resistant rated separation indicated so the assumption would be that the project is being proposed as "non-separated" occupancy classification and compliance with IBC Section 508.3 would be required. In those circumstances, the entire facility must be protected in accordance with the most restrictive requirements of the occupancies.

Though this is a renovation of an existing facility, due to the extent of renovation construction, change of use, and reconfiguration of space, it is required to comply with Codes and Standards for new construction. The primary Codes enforced for new construction are the currently adopted Life safety Code (NFPA 101 - 2012) and the International Building Code (IBC - 2012) in addition to Orleans Parish and City of New Orleans ordinances and the additional Standards referenced by those Codes.

Upon review of the current revised documents under consideration for this project, the following issues are observed and deemed appropriate for comment:

1. The first floor of 1036 Esplanade was originally occupied as mercantile occupancy classification. That space has now been defined as what appears to be dining facilities and attached commercial kitchen defined in the IBC as occupancy Group A-2. For purpose of understanding, Group A-2 is defined as:

Assembly uses intended for food and/or drink consumption including, but not limited to:

- a. Banquet halls
- b. Casinos (gaming areas)
- c. Nightclubs
- d. Restaurants, cafeterias and similar dining facilities (including associated commercial kitchens)
- e. Taverns and bars
- The commercial kitchen exhaust at the roof appears to be within 20 feet of the open patio of the adjacent residence. While not necessarily a Code issue, the grease laden aromatic vapors produce by the volume of cooking at this facility would prove objectionable which was noted in prior VCC comments.

- 3. Occupant load calculations in the submitted plans do not appear to be as defined by the various Codes and Standards enforced by the Louisiana State Fire Marshal or the City of New Orleans. Those methods are documented as follows:
 - a. Demarcation of a "path of egress" within assembly areas intended for use as dining facilities so as to exclude those paths from areas used to calculate the occupant load is not found in either the NFPA 101 or the IBC in dining rooms. The result provides for an artificially reduced occupant load.
 - b. The occupant load (number of occupants in a space) of a dining area is calculated at 15 square feet per occupant based on the entire area to be occupied with the exception of fixed obstructions such as cabinetry or appliances used for service or structural members. Alternatively, fixed seating can be used and counted as such. No fixed seating was indicated, only an area designated for such.
 - c. Calculation of occupant load based on 15 square feet per occupant at the first floor interior dining areas indicated on the plans appears to be at least 60 as the area in question appears to enclose approximately 907 square feet excluding corridors and the bar. The plans indicate an occupant load of 57 without specifically showing the individual "fixed seating.
 - d. In addition, the exterior Dining under the canopy and the courtyard area having the same occupancy use must have the occupant load calculated at 15 square feet per occupant in accordance with the adopted codes.
- 4. This interior dining is proposed to egress through the area labeled "EXTERIOR PATIO". Again, the "egress path" demarcation falsely reduces the actual occupiable area to project an occupant load less than the appropriate calculations would provide. The Codes do not provide for reduction of occupant load due to egress paths which are properly included in the area used in the calculations.
- 5. A means of egress is proposed through an alleyway between this project and the adjacent residence. That alleyway has been measured at 32 inches maximum with reduction at the gate point by utility meters and electrical panel. That route is just to the left of a door indicated as an ADA Accessible door. The indicated route of egress to the public way from that door is through this alleyway thus designating the alley as an accessible route. Investigation of the 2010 ADA/ABA adopted for review by the State Fire Marshal does not indicate that the width is sufficient for accessible egress. The minimum egress width would require not less than 44" in accordance with the NFPA 101 and IBC and additionally would require fire resistance rated corridor protection which is not indicated. Attached photographs indicate the existing electrical panel and other meters protrude into the egress width up to 10" into the clear width in an accessible route. In accordance with the 2010 ADA Standard Section 307.2, protrusion is limited between 27 and 80 inches above the floor of an accessible route to 4" into an accessible route which further precludes this alley from use as an egress route.
- 6. Additional route protection includes the following issues observed:
 - a. Rated corridor protection (minimum one hour is required but neither property appears to have those exterior bearing walls rated in accordance with IBC Table 601).
 - b. Level route (that alleyway is not paved as required by accessibility codes and standards)
 - c. Clear width (the gate at the Esplanade Avenue sidewalk exit from the alleyway is of the required 32 inches minimum measured with the gate opened 90 degrees)
- 7. The proposed dining at the second level on top of the existing filling station canopy has similar Code misinterpretations. The area there, though shown as reduced by low partitions to provide for a smaller occupant load, has the same "path of egress" demarcated so as to eliminate that path from the calculable area. The drawings indicate a calculated occupant load based on concentrated occupant load at 7 square feet per occupant and indicates a load of 77 occupants. Additional

notations indicate that somehow, the State Fire Marshal will condescend to reduce that area to an allowable 49 occupants thus permitting a single means of egress from that canopy.

The Codes in fact require the "calculated" occupant load be the minimum and do permit that load to be exceeded only if egress facilities and life safety protection are provided for the increased occupant load.

- 8. Further, regarding the seating on top of filling station canopy, the apparent area involved is 782 square feet which at 7 square feet per occupant is 112 occupants. The apparent intention with the proposed seating indicated at 7 square feet per occupant is that the space on top of the filling station canopy is to be used for concentrated load use such as found on a dance floor or other party type use similar to what is observed during Mardi Gras and other festivals in New Orleans. Due to the occupant load on the canopy exceeding 49, two means of egress are required by both the NFPA 101 and IBC from the filling station canopy but only a single means of egress is provided in these drawings.
- 9. Additional occupancy calculations are questionable at the ground floor where the only "occupied" dining area is indicated as partially under the filling station canopy. The Codes require all occupiable space in assembly occupancies to be accounted for. The entire space designated as "CATERING COURTYARD" and "EXTERIOR PATIO" is occupiable and while planters and other devices are indicated on the drawings, precise delineation of the occupiable space is not indicated. The NFPA 101 in Table 7.3.1.2 for Occupant Load Factors requires assembly use areas of "Less concentrated use, without fixed seating" to use 15 square feet for the net square footage of the area. Additional information is required to determine the precise occupant load allowed. The area in question appears to have a scaled square footage of 3,085 which when divided by 15 produces a calculate occupant load at the outdoor dining and patio of 206 occupants.
- 10. The total calculated occupant load of the ground floor dining and courtyard areas appear to be **272** in addition to the facility's upper floor of **112** for assembly in addition to the load of the residential occupancy. The apparent total occupant load then would be **384** subject to accurate dimensions and specific use being provided in future final construction drawings required for review.
- 11. Structurally, the existing filling station canopy, being a roof provided for weather protection, was not intended for human occupancy. If built under current Codes that canopy would have in addition to the loads imposed by the structure itself a required live load of 20 pounds per square foot which is sufficient for typical loads imposed by weather. However, the required design live load for assembly occupancy as proposed is 100 pounds per square foot [see *IBC Table 1607.1*]. This required load is 500 percent greater than the design capacity requirements of a filling station canopy. There is no evidence of increased structural support for that required load. If preservation of this existing facility is of concern, then any structural modifications should meet the local ordinances for preservation.

Though the drawings available for review are incomplete without any precise dimensions, I was able to transform them into drawings from which all dimensions and areas noted above were garnered. In my opinion, no further permissions should be granted without full submittal to the State and Local authorities and receipt of documents indicating compliance with the Codes and Standards and accessibility requirements for mobility impaired persons.

Should any questions arise regarding any of the comments above, please feel free to contact me.

Sincerely;

Robert Miller Architect

Photographs of alley:






Photo showing building electrical panels and utility meters protruding into alley



Alley from public sidewalk showing the gate and unleveled ground surface Also shows plumbing drain cleanout and hose-bibb protrusion into alley



Utility panel box protruding into ally between gate and public sidewalk Note the non-level walking surface between the gate and public sidewalk

	¥	
	·	



ROBERT L MILLER

A R C H I T E C T 1491 West Highway 98 Mary Esther, Florida 32569 850-581-2174 - Phone 850-581-0295 - FAX RLM@RLMarch.com

BUILDING CODES CONSULTANT
CONTINUING ÉDUCATION SEMINARS
PROFESSIONAL WITHESS
ARCHITECTURAL SERVICES

Curriculum Vitae - April 5, 2013

Robert Miller has been engaged in one fashion or another in the construction industry since the late 1960's. Miller is a native of Lake Charles, Louisiana, and was raised in the construction industry in the Miller family businesses of architecture and general contracting.

Licensed Architect - State Board of Architectural Examiners in Louisiana - 1979 to present

Education - Attended Louisiana State University and University of Southwest Louisiana school of architecture.

Retired – from Louisiana State Fire Marshal after 13 years in November 2006 where he served as a senior Staff Architect reviewing construction documents for Code compliance.

Code Instructor and Consultant - since 2001 while serving at the Fire Marshal's office where he taught application of the codes and standards enforced by Louisiana for Architects and Engineers at Engineering Society and AIA sponsored seminars and for State Fire Marshal and municipal Fire Prevention District building inspectors.

Miller has more than 40 years experience in the construction industry including general contractor, architectural specialty contractor, architectural practice, and building code official.

In November of 2006, Miller founded a consulting firm, The Building Code Institute, LLC, providing continuing education seminars and a code consulting practice for firms in several States including Louisiana, Indiana, Mississippi, Oklahoma, Arkansas, Tennessee, New Jersey, and North Carolina.


The seminars provided by The Building Code Institute are designed to communicate the correlation between the codes and the design process that provides the participant with a better understanding of the Codes used in the Design process. The seminars include life safety issues such as fire resistive construction, firestopping, egress, handicap accessibility, slip and fall prevention, and fire protections systems such as fire alarms and sprinkler systems.

Miller's architectural consulting practice includes review of design documents during the design development phase through to construction documents and assisting owners, architects, and developers with plan submittal for permitting at the State and local level. These services are in addition to performing design services as the professional of record. Professional witness services regarding Code compliance is also available.

Miller is a Professional member of the International Code Council and the National Fire Protection Association and maintains current documents and membership in those organizations.

Miller has provided code consultation on many projects across Louisiana including but not limited to:

- Julia Street Cruise Line Terminal New Orleans Egress and Life Safety design consultation
- Benson Towers (home of the State Office Building in New Orleans)
- Village de Jardin apartment/dwelling complex and Congregate Living Facility New Orleans
- Canterbury House Apartment complexes in New Orleans, Baton Rouge, Slidell, and Lafayette and in various location in Indiana and Illinois
- Design Architect for RE/MAX First Office Building Baton Rouge
- Design Architect for renovations to First Methodist Church Fort Walton Beach, FL
- Design Architect and General Contractor for J. W. Barrois Dental Office, Lafayette, LA
- Barronne Street high rise apartment building renovations New Orleans
- Rapides Parish Coliseum Renovations and Additions Alexandria, LA Code Consultant




Contact: Robert Miller - 850-581-2174 - Email: RLM@RLMarch.com - Web Site: www.RLMarch.com

Miller's Report calculates that 272 people can be held within the ground floor dining and courtyard area. Another 112 people can be held on the rooftop.


That's 384 people.

Here is an illustration of Café Habana with just 200 people.



Miller's report calculates that the property can hold 384 people.

Here is an illustration of Café Habana with 400 people.



	·		

<u>AFFIDAVIT</u>

STATE OF LOUISIANA PARISH OF ORLEANS

BEFORE ME, the undersigned Notary, came and appeared: ARNO S. BOMMER

A person of the full age of majority, domiciled in Harris County, Texas, who, after being duly sworn, did depose and say:

That he is employed as a consultant certified by the Institute of Noise Control Engineering, specializing in the science of acoustics, noise and vibration at Collaboration in Science and Technology Inc., in Houston, Texas;

1. Board Certification

I am board certified by the Institute of Noise Control Engineering, a process that involves qualifications and rigorous testing.

2. Previously certified by the Civil District Court as an expert in noise measurement and interpretation of the City of New Orleans Noise Ordinance and methodology previously relied-upon by Judge Ethel Simms Julien, in finding a nuisance bar in violation of injunction.

In previous cases, Hon. Ethel Simms Julien and the Hon. Christopher Bruno accepted me as an expert in noise and relied upon my findings.

I offer the following opinions with respect to the Café Habana based on the plans dated November 18, 2014:

- 1. A typical "busy" restaurant sound level is about 65 dBA. A very noisy restaurant can be 80 to 85 dBA.
- 2. The outdoor portions of Café Habana may occasionally exceed 80 dBA.
- 3. People tend to talk louder when there are other nearby sources of noise. The traffic on N. Rampart and Esplanade as well as the HVAC equipment and proposed fountains will provide background noise that patrons will have to speak over, causing them to speak with raised voices.
- 4. When the curtainwall doors are open, there will be two effects. By itself, the added noise from under the canopy might raise sound levels in the patio by 1 to

- 5 dBA. In addition, this increase may also cause the people in the patio area to speak louder, further increasing levels.
- 5. Other potential source of excessive community noise include HVAC condensing equipment at grade by the stairwell, a condenser unit on the roof, kitchen hood exhaust vents, doors slamming, and wait staff handling plates, trays, and silverware.
- 6. Although the existing two buildings along the residential property line provide a partial noise barrier, there is a large gap between these buildings adjacent to the stairs with only a low wall (about 6-ft tall). Sound from the courtyard and patio can travel directly through this gap to the adjacent residences.
- 7. The top of the stairs and 2nd-floor walkway are located right at the gap between the buildings. It appears from the plans that people on these stairs and walkway can look right down onto the adjacent residential property, and any sounds they make will travel directly onto the residential property.
- 8. The existing neighboring building on Rampart can reflect sounds from much of Café Habana through the gap between the buildings towards the adjacent residences.
- 9. The roof of the existing 2-story building also has a large overhang that can reflect sound from the courtyard and patio back down to the ground at the residences.
- 10. Taking into account distance effects, sound from a 65 dBA "busy" restaurant would be reduced to about 59 dBA at 50 ft (the approximate distance from the center of the restaurant to the nearest residences). This would be steady restaurant noise. If the restaurant sounds were between a "busy restaurant" and a "noisy restaurant", then sound levels at the neighboring residences would exceed 60 dBA with an L₁₀ measurement (the sound level exceeded 10% of the time).
- 11. In addition to the steady noise from the restaurant, there are often periodic louder sounds from loud conversations (laughing, very loud talking, etc.) or from events such as things being dropped. Brief sounds from people talking on the stairs can also be very loud. These types of sounds are likely to increase maximum sound levels from the restaurant at the neighboring residences to 65 dBA or higher.
- 12. The restaurant is in the VCC zone where the nighttime ordinance is an L₁₀ of 60 dBA and an Lmax of 65 dBA.
- 13. The adjacent residences are in the VCR zone where the nighttime ordinance (after 10 pm) is an L₁₀ of 55 dBA and an Lmax of 60 dBA. The applicable limits of

- the New Orleans noise ordinance are from the receiving land use, not the use of the sound source.
- 14. The HVAC equipment is rated at 66 to 69 dBA at 10 ft. The three closest units at grade range from 3 ft to 10 ft from the property line. Although there is a 6-ft wall at the property line, there are also adjacent walls and the underside of the stairs and balcony that will reflect sound over the wall. As a result, the HVAC noise is expected to produce sound levels over 70 dBA at the property line, greatly exceeding the nighttime noise ordnance and possibly exceeding the daytime ordinance.
- 15. There is line-of-sight from adjacent residences to the rooftop kitchen vent fan and walk-in-cooler condenser. I do not have any specific noise data for these, but it is likely that they will also produce excessive noise at the property line.
- 16. The restaurant sound levels from the HVAC equipment and from patrons are expected to regularly exceed the residential noise limit of the New Orleans noise ordinance after 10 pm.
- 17. With a possible standing-room capacity of over 400 people that was testified to at a committee meeting, expected sound levels could be 10 dBA louder due to the number of added patrons plus the expected effect of patrons having to further raise their voices.
- 18. The adjacent residences at 1026 Esplanade and 1028 Esplanade have backyards that are currently shielded from traffic noise by the buildings between the backyards and the roads, and these quiet backyards and their overlooking windows will be most affected by noise from Café Habana.
- 19. The proposed establishment would significantly alter the soundscape in the adjacent residential areas, adversely affecting the neighborhood's quaintness and the *toute ensemble* of the Vieux Carre. It would increase foot traffic along N. Rampart and Esplanade. Not only would patrons make sound within the site, they would also make sound from sidewalks while they are on a waiting list for a table. Because of this, the increased noise effect would spill out from the restaurant into the surrounding area.

The foregoing facts are known personally to Affiant, Arno S. Bommer.

ARNOS BOMMER

Sworn to and subscribed before me, This 7th day of January, 2015.

(Notary Signature)

(Print Notary name and #)
Notary Public
State of Louisiana

Stephen H. Wussow, Notary Public and Attorney at Law (LSBA No.35391) 355 Canal Street, Suite 2850 New Orleans, Louisiana 70130 Parish of Orleans, State of Louisiana My Commission is for Life.

CURRICULUM VITAE

ARNO S. BOMMER - PRINCIPAL CONSULTANT

Collaboration in Science and Technology Inc. 16155 Park Row, Ste. 150, Houston, TX 77084-6971 Phone: (281) 492-2784 Fax: (281) 492-1434 E Mail: arno@cstiacoustics.com

Birth Date: 25 February 1960

Birth Place: Salem, MA

Citizenship: U.S.

PROFESSIONAL REGISTRATION

Board Certified by the Institute of Noise Control Engineering (INCE)

EDUCATION

Massachusetts Institute of Technology, B.S., Architectural Design, 1982

PROFESSIONAL EXPERIENCE

MIT Energy Lab, Programmer/Researcher, 1978-1980
MIT Dept. of Architecture, Renovator, 1981
Hoover Keith & Bruce Inc., Consultant, 1982-1987
Collaboration in Science and Technology Inc., Supervisory Consultant, 1987-Present

HONORS AND SOCIETIES

Former President, MIT Alumni Club of South Texas Member, Acoustical Society of America Former Board Member, Institute of Noise Control Engineering Past Chairman, Houston Chapter of Acoustical Society of America

PROFESSIONAL RESPONSIBILITIES AND PROJECTS

At Collaboration in Science and Technology Inc. (CSTI), Mr. Bommer has worked on a variety of acoustical projects, from equipment noise tests to micro-chip manufacturing plant vibration studies.

In the field of industrial noise and vibration control, Mr. Bommer has worked in power plants, petrochemical plants, materials-processing plants, electronics manufacturing plants, offshore platforms, and aircraft

manufacturing facilities. He has worked on existing facilities and facilities in the design stage.

Mr. Bommer has conducted noise modeling and made noise and vibration measurements. He has designed treatments to reduce in-plant and community noise by reducing the sound power of the sound source, limiting the effectiveness of the sound transmission path, and isolating the sound receiver.

On legal cases, Mr. Bommer has made sound measurements, conducted modeling and acoustical calculations, and provided expert-witness testimony.

He co-authored the 2nd edition of "Noise, Vibration, and Ultrasound," Chapter 20, The Occupational Environment: Its Evaluation and Control. This is the standard industrial hygiene textbook used in the US.

CHAPTERS IN BOOKS

A House Call from Space, Booklet for Children of Parents With End Stage Renal Disease, with R. Smith, A.S. Bommer, and L.M. Bruce, 1986.

"Noise, Vibration, and Ultrasound," Chapter 20, <u>The Occupational</u> <u>Environment: Its Evaluation and Control</u>, with Arno S. Bommer and Charles T. Moritz, Salvatore R. DiNardi (ed.), AIHA, Fairfax, VA, 1997.

"Noise, Vibration, and Ultrasound," Chapter 20, <u>The Occupational</u>
<u>Environment: Its Evaluation and Control</u> 2nd Edition, with Arno S. Bommer and Charles T. Moritz, Salvatore R. DiNardi (ed.), AIHA, Fairfax, VA, 2003.

"Sound Power Level Predictions for Industrial Machinery," Chapter, Handbook of Noise and Vibration, with Arno Bommer and Charles T. Moritz, Malcolm Crocker (ed.), John Wiley & Sons, Inc., New York, NY, 2005.

OTHER PUBLICATIONS

"Cogeneration noise sources and control," with R. D. Bruce, The Journal of the Acoustical Society of America, Vol. 90, No. 4, Pt. 2, October 1991, p. 2242.

"Long-Term Ambient Sound Monitoring in National Parks," <u>Sound and Vibration</u>, with R. D. Bruce, February 1992, pp. 16-18.



"Special Concerns of Noise Control on Offshore Platforms," J. Acoust. Soc. Am., with R. D. Bruce, Vol. 92, No. 4, Pt. 2, October 1992, p. 2381.

"Cogeneration Plant Noise Analysis and Control," with R. D. Bruce and G.R. Hepler, presented at the Power-Gen Americas '93, Dallas, TX, November 1993.

"Sound isolation of an audiometric test room," with Charles T. Moritz, The Journal of the Acoustical Society of America, Vol. 96, No. 5, Pt. 2, November 1994, p. 3267.

"The Occupational Noise Book," with Robert D. Bruce, NIOSH, (in review) 2004.

"The presence of infrasound in our everyday life," with Bruce and Lefkowitz, The Journal of the Acoustical Society of America, Vol. 124, No. 4, Pt. 2, October 2008, p. 2450.

"A New Approach to Noise Control in the Workplace," with Bruce, Lefkowitz, and Levesque, Inter-Noise 2009, Ottawa, ON, CA, Aug. 2009.

"Ultrasound in the Home and Workplace," with Bruce and Lefkowitz, Inter-Noise 2009, Ottawa, ON, CA, Aug. 2009

"Making shop noise tests under difficult circumstances," with Bruce, Inter-Noise 2009, Ottawa, ON, CA, Aug. 2009


DEPOSITIONS AND TESTIMONY

Deposition regarding noise from Paving Backup Alarm. CSTI Job No. 5935. 2007. Work conducted for Willette & Guerra, LLP of McAllen, TX.

Deposition regarding noise from Funky 544. CSTI Job No. 6123. 2012. Work conducted for Smith Stagg, LLC of New Orleans, LA.

Deposition regarding noise from Old Opera House. CSTI Job No. 6123. 2012. Work conducted for Smith Stagg, LLC of New Orleans, LA.





Robert Brackin

ENVIRONMENTAL QUALITY EXPERT



Comprehensive Compliance Solutions

9744 Cal Road Baton Rouge, LA 70809

January 7, 2015

Mr. Stuart Smith
One Canal Place
365 Canal Street, Suite 2850
New Orleans, Louisiana 70130

Dear Mr. Smith,

I retired from the Department of Environmental Quality (LDEQ) on January 1, 2010 after 25 years of service. My resume is attached. I have reviewed LDEQ documents related to the remediation of property located at 1036-1038 and 1040 Esplanade Avenue in New Orleans, LA. A developer wants to build a restaurant called Café Habana at that location. I have some concerns in that respect. My concerns are as follows:

- 1) the removal of some of the contaminated soil and six steel underground storage tanks that had been buried for more than sixty years is not adequate because a significant amount of hazardous substances remains on the property.
- 2) If the ultimate purpose of air testing is to determine the potential health impact to the public and reduce uncertainty in the assessment, insufficient air testing was done during the closure. Additional testing has to be conducted prior to construction of this restaurant in my opinion.
- 3) The developer is required to notify LDEQ that the intended land use has changed so that LDEQ can re-evaluate the contaminated areas that was of interest in the remediation. (See attached conveyance notice, indicating the property has not been released for non-industrial use.) I have not found any such land use change notification in the public records at LDEQ.

4) A groundwater sample should have been taken since RECAP standards were exceeded at a

depth of 8 feet, a depth near or below the water table.

5) Soil samples should have been taken at the property line since the samples taken on the

southern end of Tank 2 and Tank 3 exceeded RECAP standards and were in close proximity to

neighboring property.

6) Insufficient testing was performed and therefore the possibility that contamination has

spread to neighboring properties cannot be eliminated.

Sincerely,

Richard Brackin

Leaaf

Mr. Tom Harris Admin.
UST and Remediation Division
LA DEQ
P.O. Box 4312
Baton Rouge, LA 70821-4312

JUN 2 1 2013

LADILLE OF FAM QUALITY
REMEMBERSHOWSERVICE & DIVISION
LOG #

RE: Conveyance Notice 1040 Esplanade Ave New Orleans, LA 70116 (Orleans Parish) Facility ID No. 36-019386

Al No. 184805

Remail His	i. Septiment Division
Manager	and the second s
Team Indiast_	and the resource of the transformation of th
AI #:	anna i paga naga naga naga na na dalaka. Maya naga naga naga na naga naga manaka naga naga naga na na naga nag
TEMPO lase a	COMMITTED TO THE STATE OF THE S
There Can	vined to

Mr. Harris:

Leaaf Environmental, LLC (Leaaf) is submitting this letter documenting the filing of the Conveyance Notice for the above referenced site.

The Conveyance Notice was filed with Orleans Parish conveyance records on June 12, 2013. The original and one (1) photocopy of the notice are attached for LDEQ records.

If you have any additional questions regarding this matter, please contact Jesse Hoppes or Jim Blazek at (504) 342-2687.

Sincerely,

Holly (2) Johnston Bookkeeper

RECEIVED

JUL 1 U

SOUTHEAST REGIONAL OFFICE

CONVEYANCE NOTICE

Esplanade NOLA LLC hereby notifies the public that the following described Area of Investigation (AOI), Louisiana Department of Environmental Quality (LDEQ) Agency Interest Number 184805, was closed with contaminant levels present that are acceptable for industrial/commercial use of the property as described in LDEQ's Risk Evaluation/ Corrective Action Program (RECAP), Section 2.17. In accordance with LAC 33:I., Chapter 13, if land use is to change from industrial to non-industrial, the responsible party shall notify the LDEQ within 30 days and the AOI shall be reevaluated to determine if conditions are appropriate for the proposed land use.

This site was closed in accordance with the Louisiana Administrative Code, Title 33:I., Chapter 13. Information regarding this site is available in the LDEQ pubic record and may be obtained by contacting the LDEQ Records Manager at (225) 219-3168. Inquiries regarding the contents of this site may be directed to Sean Meenan at 757 Fulton Street, Brooklyn, NY 11217.

AOI Description:

The former service station is located on the corner of Esplanade Avenue and North Rampart Street at 1040 Esplanade Avenue, New Orleans, LA. The AOI includes all of the former tankholds excluding the used oil tank (T-5) based on exceedances RECAP above non-industrial screening standards. Maximum analytical results for constituents of concern (COCs) at the site are summarized on Table 1.

LEGAL DESCRIPTION:

One certain piece or portion of ground, together with all the buildings & improvements thereon and all of the rights, ways, servitudes, privileges, advantages and appurtenances thereunto belonging or in anywise appertaining, situated in the State of Louisiana, Parish of Orleans, Square No. 108 of the Second Municipal District of the City of New Orleans, which square is bounded by Burgundy Street, Barracks Street, North Rampart Street and Esplanade Avenue, designated as Lot 9-X on a plan of resubdivision of Lot 3 and Pt. Lot 9 into lot 9-X dated January 21, 2013 by Gilbert, Kelly & Couturie, Inc. and is more particularly described as follows to wit:

LOT 9-X forms the corner and begins at the point of intersection of the southerly right of way line of N. Rampart Street and the westerly right of way line of Esplanade Avenue; thence in a southerly direction along the westerly right of way line of Esplanade Avenue, a distance of 31 feet 2 inches 0 lines (31.2.0) to a point; thence in a westerly direction through an interior angle of 90 degrees 32 minutes 10 seconds, a distance of 80 feet 11 inches 0 lines (80.11.0) Actual, 81 feet 1 inch 0 lines (81.1.0) Title to a point; thence widening in a southerly direction through an interior angle of 269 degrees 27 minutes 50 seconds, a distance of 33 feet 2 inches 0 lines (33.2.0) to a point; thence in a westerly direction through an interior angle of 90 degrees 32 minutes 10 seconds, a distance of



SO feet 2 inches 0 lines (50.2.0) to a point; thence in a northerly direction through an interior angle of 89 degrees 27 minutes SO seconds, a distance of 64 feet 4 inches 0 lines (64.4.0) Actual, 63 feet 11 inches 3 lines (63.11.3) Title, to a point on the southerly right of way line of N. Rampart Street; thence in an easterly direction through an interior angle of 90 degrees 32 minutes 10 seconds along the southerly right of way line of N. Rampart Street, a distance of 131 feet 1 inch 0 lines (131.1.0) back to the point of intersection of the southerly right of way line of N. Rampart Street and the westerly right of way line of Esplanade Avenue, the point of beginning. Lot 9-X contains \$,750.7\$ square feet. The improvements thereon bear Municipal Nos. 1040 Esplanade Avenue and 1310-12-14 N. Rampart Street, New Orleans, Louisiana 70116.

signature of Person Filing Parish Record

86/04/13

(A true copy of the document certified by the parish clerk of court must be sent to the Underground Storage Division -Regional Office of site location

TABLE 1: SOIL ANALYTICAL DATA SHOWING THE HIGHEST CONCENTRATION REMAINING ON-SITE OF THOSE COCS ABOVE THE NON-INDUTRAIL SCREENING STANDARD.

1040 Esplanade Avenue, New Orleans, LA (Sitewide AOI)

	Location of Maximum	Depth of Maximum	Maximum Concentration	SOIL_SSni RECAP	SOIL_SSI RECAP
Constituent of	Concentration	Concentration	Remaining on	Standard	Standard
Concern (COCs)	in Soil	in Soil (ft. bgs.)	Site (mg/kg)	(mg/kg)	(mg/kg)
TPH-GRO*	T1-S	8'	762*	65	510
Aliphatic (>C8-C10)	T-1S	7,	366	120	880
Aromatics (>C8-C10)	T-IS	7,	185	65	510
TPH-DRO**	T-1S	8'	583**	65	510
Aromatic (>C10-C12)	TIS	8'	183	120	1,100

mg/kg - Milligrams per Kilogram

Ft bgs - Feet below ground surface

TPH-GRO - Total Petroleum Hydrocarbons - Gasoline Range Organics

TPH-DRO - Total Petroleum Hydrocarbons - Diesel Range Organics

 $RECAP - \underline{R}isk \ \underline{E}valuation \ \underline{C}orrective \ \underline{A}ction \ \underline{P}rogram$

SSni - Screening Standard for soil protective of human non-industrial exposure

SSi + Screening Standard for soil protective of human industrial exposure

Notes:

Bold Values show exceedances above applicable RECAP Standards

*TPH-GRO results were superseded by VPH Fractions

**TPH-DRO results were superseded by EPH Fractions

